

District 8 Competition

Monday, January 20, 2020

Keystone+Mountain+Lakes

Carpenters Training Center

652 Ridge Road

Pittsburgh PA. 15205

(412) 262-1830





Location Chair - John Brown 412-847-1944 or john.brown beattietech.com



Carpentry Competition Overview

- Cell Phones or wearable electronics are not permitted at any time even if powered off.
- There are no official clothing requirements at the District level.
- All competitors must wear trade appropriate clothing and safety equipment that follows ALL trade safety rules.
- Resumes are not needed at the District level.
- If there is a question about the contest, please contact the SkillsUSA site corrdinator.

Contestants must provide all hand and power tools including but not limited to:

Hand Tools:

- Personal Tools (Hammer, Tape Measure, Square, etc.)
- Framing Square, Stair Gauges
- 2' and 4' Levels
- Hand Saws

Power Tools:

- Portable Circular Saw
- Reciprocating Saw
- Cordless Drill
- Extension Cord

*Students may bring more tools if they desire. Your school and The KML Carpenters' Training Center are not responsible for lost, stolen, or damaged tools.

Competition Overview

Students will complete the following framing tasks as per drawings provided for the project.

Wall Framing: Tasks will include, but are not limited to, conventional wall layout, framing and construction and also proper bracing, sheathing, nailing and rough in will be evaluated.

Roof Framing: Tasks will include, but are not limited to, layout, cutting and installing roof rafters.

Material List

(Provided by the KML Carpenters' Training Center)

- 18 2x4x8'
- 2 2x6x12'
- 1 1'x8' rip of 7/16 OSB
- 1 5 lbs. box of 16d common nails
- 1 5 lbs. box of 8d common nails

Note: Contest blueprints will NOT be given out before the day of competition. Please prepare based off the National Technical Standards. All work must meet standard practices and Codes.

Items Evaluated	Possible Points				
Wall Framing					
Studs Crowned	10 10 10 10 10 10 10 10 10 10 10 10 10 1				
Studs 16" o.c.	10				
Nailing sequence	10				
XBX Corners	10				
Joints tight	10				
Wall #1 8'x4'	10				
Wall #2 2'x4'					
Door R.O.	10				
Door CL	10				
Window R.O.	10				
Window CL	10				
Window square	10				
Cripples	10				
Safety	20				
Total	150				
Rafters					
Tail, plumb					
4" Seat cut					
Cuts accurate					
Joints tight	Shi Age 20th				
Nailed to top plate 3-16d					
Nailed to ridge 3-16d					
12" Projection with Facia					
4/12 Pitch	10				
Layout	10				
Safety	20				
Total	100				
General					
Material usage	10				
Construction sequence	10				
Completion time	30				
Total	50				
Total Score	300				

Items Evaluated	Possible Points	Team									
		1	2	3	4	5	6	7	8	9	10
Wall Framing											
Studs Crowned	10										
Studs 16" o.c.	10										
Nailing sequence	10										
XBX Corners	10										
Joints tight	10										
Wall #1 8'x4'	10										
Wall #2 2'x4'	10										
Door R.O.	10										
Door CL	10										
Window R.O.	10										
Window CL	10										
Window square	10										
Cripples	10										
Safety	20										
Total	150										
Rafters											
Tail, plumb	10										
4" Seat cut	10										
Cuts accurate	10										
Joints tight	10										
Nailed to top plate 3-16d	5										
Nailed to ridge 3- 16d	5										
12" Projection with Facia	10										
4/12 Pitch	10										
Layout	10										
Safety	20										
Total	100										
General											
Material usage	10										
Construction	10										
sequence	3.8			7							
Completion time	30										
Total	50			10.10.404.00							
Total Score	300										